

1. VERIFY SIZE AND LOCATION OF OPENINGS WITH ARCHITECTURAL AND MEP DRAWINGS.
2. CONTRACTOR IS RESPONSIBLE FOR BRACING AND PROTECTING THE EXISTING STRUCTURAL ELEMENTS FROM DAMAGE, CORROSION, OVERLOADING, ETC. DUE TO CONSTRUCTION OPERATIONS AND/OR WEATHER ELEMENTS.
3. TEMPORARY SHORING MUST BE DESIGNED AND STAMPED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF MICHIGAN.
4. REMOVE DETERIORATED LINTEL COVER PLATE. VERIFY IN FIELD SIZE AND CONDITION OF EXISTING LINTEL AND INFORM ARCHITECT/ENGINEER IF LINTEL IS IN POOR CONDITION.
INSTALL NEW STEEL LINTEL COVER PLATE. COORDINATE WITH ARCH FOR COATING COLOR.
5. SISTER EXIST. DETERIORATED/DAMAGED JOIST WITH 1 3/4"x11 7/8" LVL JOIST (FULL LENGTH) W/ 3 ROWS 1/4"x3 1/2" SIMPSON SDS SCRS @ 16" W/ MIT SIMPSON HANGER, NAIL THE DECKING TO NEW JOIST W/ 10d COMMON NAIL @ 6" O.C. MAX. REFER TO S600 THRU S620.
6. REMOVE AND REPLACE DETERIORATED/DAMAGED DECK W/ 3/4" EXTERIOR GRADE DECK. NAIL THE DECKING TO JOISTS W/ 10d COMMON NAIL @ 6" O.C. MAX.
7. PROVIDE SUPPORT/REPAIRS WHERE EXISTING JOIST SEATS ARE NOT SUPPORTED AND ARE REQUIRED. REFER TO S5500.

S101-E

